



Notice Inviting Tender

Tender No: 20/AR.REG/22-23

Date: 27.06.2022

Sealed quotations are invited from bonafide Contractor for **Supplying laying of paver block (Balance work) at the garrage and other miscelleneous work.**


The quotation will be received in the drop box/ concerned section.

Important Information	
Drop at	Stores & Purchase Section
Start date of tender Submission	27.06.2022
Time	Between 11:00 am and 5:00 pm (on all working days)
Last date of tender submission	06.07.2022 at 02:00 pm
Tender Opening date	To be notified later via e-mail/phone/SMS by the office of the Superintendent Engineer.
Tender Opening place	

REGISTRAR

Terms & Conditions: -

1. To qualify for award of the contract the bidder should have valid civil license and should have satisfactorily completed at least one similar work.
2. Quotation are to be submitted as per above mentioned format along with GST, PAN, Valid Trade License.
3. All rates quoted should be inclusive of all taxes, levies & duties and Labor Welfare Cess, the rates should be quoted both in figures and words. Request for inclusion of any tax/levy at later stage will not be entertained.
4. Transportation, Packing, Forwarding and Insurance Charges if any to be charged should be specifically indicated.
5. The Institute reserves the right to accept or reject all or any of the tenders without assigning any reason whatsoever. The decision of the Institute shall be final in case of any dispute.
6. The work should be completed within 15 days of issuing of order.
7. Materials & accessories supplied/used should be as per specification and of Approved Quality (B.I.S.) or by the authorised officer of IEST, Shibpur.
8. The work should be completed within stipulated period as indicated in the work-order. A Liquidated damages @ 0.5% per week, subject to maximum of 10% of the value of work-order, beyond which the Employer may cancel the Contract.
9. Bills in Triplicate should be presented for payment within 15days of supply/completion of work.
10. The Order no. is to be noted on both challan & Bill.
11. All bills are to be accompanied by order copies and challans as received.
12. Payment will be made within 60 days of Submission of proper bills, challans etc. by A/c payee cheque, no Cash payment will be made under any circumstances.
13. Date of submission of quotation is **06.07.2022 up to 02:00 pm at the Stores & Purchase Section.**
14. **Date & place for opening of tender will be notified later by the office of the Superintendent Engineer.**


(D. Chakrabarty)
Assistant Registrar
Stores and purchase

Copy forwarded for information and necessary action to:

1. Institute Website
2. All Notice Board
3. Suptd. Engineer, IEST, Shibpur

BOQ FOR THE WORK OF: Supplying laying of paver block (Balance work) at the garrage and other miscellaneous work

Sl. No	Description of items of work (Based on PWD schedule of rates w.e.f. 01.11.2017.)	Unit	Unit Rate (Rs)	Quantity	Amount (Rupees)
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. (Page 1, Item 2)	Cum.	119.27	3.675	438.32
2	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) (Page 2, Item 4)	Cum.	767.91	1.838	1411.42
3	Brick soling with picked jhama bricks including preparation of bed as necessary with brick joints properly filled in and packed with powdered earth and including necessary cushion of similar material below the soling (and in between layers when more than one layer is used) completes as per direction. (a) Single brick flat soling (thickness 75 mm.) (Page 226, Item 1)	Sqm.	312.00	24.500	7644.00
4	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes.	Cum.	3722.00	2.071	7708.26
5	Supplying & laying as per IRC-SP:063-2004 paver unit of any shade of approved quality as per relevant IS code, laid in pattern as directed in pavement, footpath, driveway (paver block only), etc including necessary underlay complete in all respect with all labour and material. [Border concrete if necessary to be paid separately]. Note: Sub-grade CBR should not be less than 5. (b) 50 mm thick interlocking designer concrete paver block M- 30 grade for non-traffic zone, buiding premises, garden, parks, domestic drive as per IS: 15658-2006 (over 20-30 mm medium sand bed on 200mm thk bound gnauar /granular base course including cost of sand for sand bed but excluding cost of base course & subgrade preparation.) (ii) Coloured Decorative (Page 74,75, Item 48 (bi))	Sqm.	1123.00	24.500	27513.50
6	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge.(White cement, synthetic adhesive and grout material to be supplied by the contra conc (II) With Polymerised Adhesive [6 mm thick] & epoxy grouting materials for filling joints including spacer-2 mm [Applied directly over finished artificial stone floor/ mosaic etc.] (Page 48, Item 16)	Sqm.	1789.00	8.400	15027.60
				A. Total	59743.098
				B. Add GST @ 12%	7169.17
				Labour welfare cess@1% of C.	597.43
				C. Cost of work	67509.70

To qualify for award of the contract the bidder: -

(a) should have satisfactorily completed as a prime contractor at least one similar work of value not less than Rs. 1,00,000/- (Rupees one lakh only)

Security Deposit:

The employer shall retain 10% from each payment due to the contractor as security deposit which shall be released when the Period of Maintenance has passed and Engineer has certified that all defects notified by the Engineer to the Contractor before the end of this period have been corrected.

Period of Maintenance.

The "Period of Maintenance" for the work is twenty four months from the date of taking over possession of the completed works or one full monsoon season whichever occurs later. During the period of maintenance, the contractor will be responsible for rectifying any defects in construction free of cost to the Employer

I / We offer to execute the Works described in the Bill of Quantities of the Tender Document in your letter / tender no referred to above in accordance with the Conditions of Contract enclosed therewith at _____ percentage above / below (*) the estimated rates, i.e. for a total Contract Price of

Rs. _____ [in figures] *

Rs. _____ [in words]"

Authorized Signature :

Date: _____